

AD-A093 761


CONSTRUCTION ENGINEERING RESEARCH LAB (ARMY) CHAMPAIGN IL F/G 13/2  
PAVEMENT EVALUATION AND REPAIR RECOMMENDATION SIERRA ARMY DEPOT--ETC(U)  
NOV 80 M Y SHAHIN  
IAO-PR-9-80

UNCLASSIFIED

CERL-TR-M-283

NL

END  
DATE  
FILMED  
2-84  
DTIC



MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

12

construction  
engineering  
research  
laboratory



United States Army  
Corps of Engineers  
... Serving the Army  
... Serving the Nation


TECHNICAL REPORT M-283  
November 1980

AD A093761

LEVEL II

PAVEMENT EVALUATION AND  
REPAIR RECOMMENDATION  
SIERRA ARMY DEPOT, AMEDEE AIR STRIP

M. Y. Shahin



DDC FILE COPY

DTIC  
ELECTE  
S JAN 13 1981 D

C



Approved for public release; distribution unlimited.

81 1 13 007

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

***DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED  
DO NOT RETURN IT TO THE ORIGINATOR***

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER 14 CERL-TR-M-283	2. GOVT ACCESSION NO. HD 4093.761	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) 6 PAVEMENT EVALUATION AND REPAIR RECOMMENDATION SIERRA ARMY DEPOT, AMEDEE AIR STRIP		5. TYPE OF REPORT & PERIOD COVERED 7 FINAL
7. AUTHOR(s) M. Y. Shahin 10 Mohamed Y. Shahin		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY P.O. Box 4005, Champaign, IL 61820		8. CONTRACT OR GRANT NUMBER(s) 15 IAG-PR-9-80
11. CONTROLLING OFFICE NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 12 661
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE November 1980
		13. NUMBER OF PAGES 62
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Copies are obtainable from National Technical Information Service Springfield, VA 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Sierra Army Depot, CA maintenance Amedee Air Strip repair runways pavements		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The Pavement Condition Index (PCI) procedure was used to evaluate five alternatives for repairing the runway of the Amedee Air Strip, Sierra Army Depot, California. Based on the PCI analysis, it was recommended that the old surface be recycled and used as a base, with a new asphalt concrete surface added to a depth of 3 inches at the central 75 feet and tapered to 1 inch at the edges. This recommendation was based on the assumption that the engineer has flexibility in specifying the type and grade of asphalt needed. If not, reconstruction with concrete may be economically justified based on life cycle costs.		


DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

410.279

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

## FOREWORD

This research was conducted for the Sierra Army Depot, Herlong, CA, under IAO PR 9-80 by the U.S. Army Construction Engineering Research Laboratory, Champaign, IL. The Sierra Army Depot Project Monitor was Mr. Michael P. Balerviez. The CERL Principal Investigator was Dr. M. Y. Shahin.

The following people are acknowledged for their participation in surveying the runway: Mssrs. Mike Flaherty and Jim West, DARCOM; Mssrs. Mike Balerviez, Ray McMillan, and David Wickward, Sierra Army Depot. Dr. R. Quattrone is Chief of CERL-EM. COL Louis J. Circeo is Commander and Director of CERL, and DR. L. R. Shaffer is Technical Director.

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A	

## CONTENTS

DD FORM 1473	1
FOREWORD	3
LIST OF FIGURES AND TABLES	5
1 INTRODUCTION .....	7
Background and Description of Existing Facility	
Objective	
2 INVESTIGATION .....	7
Runway Condition Survey	
Field Investigation	
Laboratory Investigations	
3 EVALUATION .....	8
Evaluation of Past Performance and Selection of	
Feasible Maintenance and Repair (M&R) Alternatives	
Prediction of Future Performance of	
Selected M&R Alternatives	
Life-Cycle Costing of Selected	
M&R Alternatives	
4 CONCLUSIONS AND RECOMMENDATIONS .....	10
FIGURES AND TABLES	11
APPENDIX A: PCI Computer Output	35
APPENDIX B: Results of AC Laboratory Testing	50
APPENDIX C: Program Output of PCI Prediction	
for Each M&R Alternative	53
APPENDIX D: Program Outputs for Predicting	
Future Cracking	55
APPENDIX E: Future M&R Costs for Each M&R Alternative	57
DISTRIBUTION	



## FIGURES

Number	Page
1 Layout and Typical Sections Amedee Army Airfield	11
2 Division of Runway Into Features	12
3 Division of Features Into Sample Units	13
4 PCI of Individual Sample Units for Central, North, and South Features	14
5 Photograph of Sierra Army Depot, Amedee Runway, Showing Primary Type of Distress	15
6 Runway Layout Showing Location of Cuts	15
7 Cut #1	16
8 Cut #2	17
9 Cut #3	18
10 Tensile Strength Vs. Temperature for AC Surface Top 1.5 Inch	19
11 Data Used in Temperature Cracking Program	20
12 Predicted Cracking Using Temperature Cracking Program	21
13 Airfield Pavement Condition Evaluation Summary	22
14 Correlation of M&R Zones With PCI and Condition Rating	23
15 Rate of Deterioration of AC Pavements	23
16 Evaluation of Load Carrying Capacity	24
17 Expected PCI Over Time for Each M&R Alternative	25
18 Alternative A: Continue Crack Seal to PCI=40 (1987), Then Overlay	26
19 Alternative B: Overlay 1980	27
20 Alternative C: Replace Surface — 3-Inch Deep	28
21 Alternative D: Recycle Surface and Use as Base, Add New Surface	29

22	Alternative E: Replace Surface Central 75 Feet, Crack Seal Outside	30
23	Life Cycle Costing of M&R Alternatives	31

## TABLES

Number	Page
1 Summary of Linear Cracking for Entire Runway	32
2 Summary of Distresses Other Than Linear Cracking	32
3 Predicted Cracks and Repair Costs for Entire Runway	33
4 Summary of Linear Cracking Outside the Central 75 Ft	33
5 Predicted Cracks and Repair Cost for Outside the Central 75 Ft	34
6 Comparison of \$/Unit Performance for Each M&R Alternative	34
B1 Bituminous Mix Analysis	50
B2 Indirect Tensile Results	51
B3 Sample Size	51
B4 Computation of Indirect Tensile Strength	52

# PAVEMENT EVALUATION AND REPAIR RECOMMENDATION SIERRA ARMY DEPOT, AMEDEE AIR STRIP

## 1 INTRODUCTION

### Background and Description of Existing Facility

Amedee Air Strip is located at Sierra Army Depot, Herlong, California, east of Honey Lake and 50 air miles northwest of Reno at an elevation of 4000 feet.

A layout of the runway is shown in Figure 1. The runway surface is a 3-inch layer of asphalt concrete (AC) which, with the 4-inch crushed base below, was added in 1969. The original runway was constructed in 1943, and the 1969 overlay was emplaced because of considerable cracking in the original surface. The 4-inch crushed stone base was used to eliminate (or minimize) reflection cracking in the new surface.

Since its overlay in 1969, the runway has had a history of problems, and experts from Office, Chief of Engineers (OCE), Sacramento District Engineer Office, Defense Acquisition and Readiness Command (DARCOM), Depot Systems Command (DESCOM), and the U.S. Army Corps of Engineers Waterways Experiment Station (WES) have made on-site evaluations of its condition. These evaluations showed that although the runway appears to be structurally sound, the pavement has oxidized, causing surface cracks. It was also concluded that the cracks are not reflective cracks from the old pavement constructed in 1943.

The cost of maintaining the runway from 1969 to 1979 has been \$320,550, and is increasing rapidly.

### Objective

The objective of this study was to determine the optimum maintenance and repair alternative for Amedee Airfield.

## 2 INVESTIGATION

### Runway Condition Survey

On 13-15 November 1979 a team from DARCOM, the Sierra Army Depot, and CERL performed

a condition survey of the runway using the Pavement Condition Index (PCI) procedure developed by CERL and implemented by the U.S. Air Force worldwide.<sup>1</sup> The runway was divided into distinct features based on structural composition and traffic distribution as shown in Figure 2. Each feature was divided into sample units for inspection. The number and location of sample units inspected were determined as shown in Figure 3. A PCI inspection was performed on all the runway features, and the results are shown in parentheses in Figure 2. Figure 4 shows a plot of the PCI for the individual sample units of each feature, and Appendix A provides a complete PCI computer output.

The results of the PCI survey (Appendix A) showed that the distress is mostly linear cracking. Figure 5 is a photograph of the runway surface. Table 1 summarizes the quantities and severities of linear cracking found in each feature and Table 2 summarizes the other distresses that were found.

### Field Investigation

From the PCI inspection, it was determined that the majority of the cracks are temperature related; however, whether the distress was reflective, started from the base course (i.e., bottom-up), or started from the surface (i.e., top-down) was not clear. Therefore, three cuts (approximately 1 x 2 feet) were made around the different cracks so that their cause and characteristics could be clearly determined (Figure 6). Cuts #1 and #3 were outside the traffic area, and cut #2 was in the traffic area.

Cut #1 (Figure 7) was across a 4-inch-wide crack extending through the full depth of the top AC surface. There was no evidence of the crack in the base or on the old AC surface below.

Cut #2 (Figure 8) was made across two cracks, one of medium severity and one of low severity. Both cracks were continuous throughout the full depth of the top AC surface but not through the base or old AC surface. The low-severity crack was only about 1½ feet from the medium-severity crack and both were in the wheel path, as indicated by the tire markings. These two cracks were also beginning to be connected by random cracking. It was evident that the initial temperature cracking was becoming alligator cracking because of the weakened pavement condition around the temperature cracks.

<sup>1</sup>Airfield Pavement Evaluation Program, AFR 93-5 (Department of the Air Force, 1980).

Cut #3 (Figure 9) was made across the tip of a hairline crack in a nontraffic area. The cut showed that only portions of the crack had propagated to the bottom of the AC surface. In Cut #3, the surface crack was 8 inches long and only 3 inches had propagated to the bottom. Therefore it was concluded the crack had originated at the surface.

Based on the field investigation, it was concluded that the cracking in the Sierra Army Depot runway is limited to the AC surface. Furthermore, it was speculated that the temperature cracks are caused by thermal fatigue in the AC surface resulting from the high daily temperature cycling variation in this area.

#### Laboratory Investigations

The laboratory investigations were designed to verify field observations that the AC surface had oxidized and that the cracks were caused primarily by thermal fatigue cracking. The AC slabs obtained from the three cuts described above were forwarded to WES for testing. Appendix B provides the results of the testing.

Tests performed included: AC Marshall Stability, flow, percent voids in total mix, percent voids filled; and asphalt penetration, softening point, and viscosity. The results showed that the pavement had oxidized, as indicated by a penetration of 15 and softening point of 71.2°C (160°F) for the asphalt in the surface course.

Construction records from 1969 showed that the asphalt had an original penetration of 90 and a softening point of 49.4°C (121°F). The construction records also showed that penetration (percent of original) after the Thin Film Test was 72. The drop in penetration from 90 in 1969 to 15 in 1979 is considered high.

In addition to the above tests, the indirect tensile test was performed at four temperatures (-20, 20, 50, and 75°F) at loading rate .05 inches/minute, and at three temperatures (20, 50, and 75°F) at loading rate 2.0 inches/minute. Figure 10 is a plot of the tensile strength of the AC mix (top 1.5 inch) versus temperature.

To verify the cause of cracking, the program developed by Shahin<sup>2</sup> was used. The program predicts both low-temperature and thermal-fatigue cracking as

a function of the AC mixture properties and climatic factors. Figure 11 shows the input to the program. Figure 12 is a plot of cracking versus age as predicted from the program. As shown in the figure, there is a close agreement between the measured and predicted amounts of cracking.

Detailed analysis of the program output showed that the cracks are caused by thermal fatigue cracking (resulting from daily temperature cycling) rather than just simple low temperature. The close agreement in prediction is encouraging in that the same program can be used for future mix design and selection of optimum asphalt grade to minimize cracking. It is believed that a careful mix design and careful selection of asphalt grade can increase the pavement life by several years.

### 3 EVALUATION

#### Evaluation of Past Performance and Selection of Feasible Maintenance and Repair (M&R) Alternatives

The evaluation, which was performed according to the M&R guidelines CERL developed for the U.S. Air Force,<sup>3</sup> was performed for feature RC3 since it is the largest feature, receives most of the traffic, and has the lowest PCI. Following is a brief discussion of the results, which are summarized in Figure 13.

1. The PCI of the feature is 61, which locates the feature in an M&R zone of routine, major, and overall. This is based on the guidelines shown in Figure 14, which were developed by a group of experienced Air Force engineers and subjected to considerable field testing and validation. It is to be noted that the M&R zone reflects needed M&R within 2 years of the PCI survey date.

2. Localized variation exists. Variation results because one sample unit has a PCI of 33 (sample unit #20), while the average PCI of the feature is 61.

3. The long-term rate of deterioration is high compared to other airfield AC pavements of the same

<sup>2</sup>M. Y. Shahin, "Prediction of Low-Temperature and Thermal-Fatigue Cracking in Flexible Pavements," Ph.D. Dissertation (University of Texas at Austin).

<sup>3</sup>M. Y. Shahin, *Development of a Pavement Maintenance Management System, Vol VI: M&R Guidelines—Validation and Field Applications*, ESI-TR-79-18 (USAF Engineering and Services Center [AFESC]).

age throughout the United States. This is illustrated in Figure 15.

4. Analysis of the load-carrying capacity showed the pavement to be structurally adequate (see Figure 16). Distress evaluation showed that 56 percent of the deduct value stem from load-associated distress (alligator cracking). However, this can be attributed to the weakened areas adjacent to cracks caused by temperature variations.

Application of the M&R Performance Standards recently developed for the U.S. Air Force\* to the results of the evaluation in Figure 13 showed that most experienced maintenance engineers would consider the following M&R alternatives:

- (a) Routine,
- (b) Surface Treatment,
- (c) Thin Overlay, and
- (d) Recycling or Replacement of Surface.

The above alternatives all seemed feasible. Selection of a specific M&R alternative is a function of future performance and life-cycle costing.

#### **Prediction of Future Performance of Selected M&R Alternatives**

Five Specific M&R alternatives were analyzed:

Alternative A: Continue to seal cracks to a minimum (acceptable) PCI; then overlay with 3-inch AC at center, tapered to 1 inch at edges.

Alternative B: Seal cracks and overlay immediately with 3-inch AC at center, tapered to 1 inch at edges.

Alternative C: Replace entire surface with a new 3-inch-deep AC hot mix.

Alternative D: Recycle surface and reuse as base; then add new 3-inch AC for central 75 feet and taper to 1 inch at edges.

Alternative E: Replace central 75 feet of surface course with 3-inch AC hot mix, and continue to crack seal outside areas.

Along with each of these alternatives, it was assumed that a rejuvenating surface treatment would

be applied periodically to retard surface brittleness and thus temperature cracking.

The PCI for each alternative was predicted, using a computer program based on M&R consequence models developed for the U.S. Air Force.<sup>4</sup> Appendix C provides the program output for each M&R alternative. Figure 17 is a plot of the expected PCI over time for each alternative.

#### **Life-Cycle Costing of Selected M&R Alternatives**

The life-cycle costing is determined based on initial cost, future M&R cost, and salvage value. The present-worth method was used to consider both interest and inflation rates. Figures 18 through 22 provide work summary and initial cost estimates for each alternative.

Future cracking had to be predicted in order to estimate future M&R cost. The maximum cracking expected to occur in the future, is block cracking with an average size of 10 feet x 10 feet. This translates into a total cracking length of approximately 197,050 linear feet for an area that is 150 feet x 6800 feet. The total amount of cracking currently existing is 51,053 feet. Using statistical techniques,<sup>5</sup> future cracks were predicted; (see Table 3). Appendix D provides the computer output used in the prediction. Future M&R was computed on a two-year basis, assuming a repair cost of \$1.0/linear foot. Another assumption in the computation of future M&R was that cracks must be resealed every 6 years. Table 3 shows all cost calculations.

For M&R Alternative E, where only the central 75 feet would be replaced, it was essential to do the crack prediction for only the outside 75 feet. Table 4 summarizes the cracking outside the central 75 feet.

The maximum cracking expected to occur outside the central 75 feet will be in the form of block cracking having an average size of 10 feet x 10 feet, or a total

\*U.S. Air Force Pavement Major Command Engineers meeting held at CERL 15-17 Jul 80.

<sup>4</sup>M. Y. Shahin, M. I. Darter, and I. T. Chen, *Development of a Pavement Maintenance Management System, Vol VII: Maintenance and Repair Consequence Models and Management Information Requirements*, FSI-TR-79-18 (AFESC, December 1979).

<sup>5</sup>M. Y. Shahin, M. I. Darter, and S. D. Kohn, *Development of a Pavement Maintenance Management System, Vol IV: Appendices A through I, Maintenance and Repair Guidelines for Airfield Pavements*, CEEDO-TR-77-44 (AFESC, 1977).

cracking length of approximately 105,325 feet. The total cracking currently existing is 18,906 feet. Using statistical techniques, future cracks were predicted (see Table 5). Appendix D provides the computer output used in the prediction. Another assumption in the computation of future M&R was that cracks must be resealed every 6 years. Table 5 shows all cost calculations.

The information in Tables 3 and 5 was used to compute future M&R costs for each alternative. (Appendix E shows the computation of future costs.) The cost information was then input to a present-worth economic analysis program. Figure 23 shows the results of the cost analysis, with ranking of alternatives based on net present cost shown at the top of the figure. Considering the amount of predictions and estimates involved, the difference in cost among the various alternatives is not large enough to allow selection of an alternative based on cost alone.

## **4 CONCLUSIONS AND RECOMMENDATIONS**

The runway AC surface had oxidized, as shown by a measured asphalt penetration of 15 (1979) versus an original penetration of 90 (1969). Large daily temperature variations (average daily temperature range of 40°F) have caused the oxidized AC surface to crack. The amount of cracking is expected to increase at a high rate, as predicted in Table 3.

Figure 2 shows the PCI of the various runway features. The lowest PCI is 61 for feature RC3, which has been caused by further breakdown of the cracks under load.

Five feasible M&R alternatives were identified and analyzed. Figure 17 shows the performance (PCI over time) expected for each alternative. Figure 23 shows the results of life-cycle costing for each alternative. The most costly alternative (C) is only about 30 percent higher than the least costly alternative. Therefore, considering the amount of predictions and assumptions necessary to perform the life-cycle costing, the difference in net present cost among the various alternatives cannot be used as a sole indicator for

selecting the best alternative. Another factor to consider is the dollars spent per unit performance. This is computed by dividing the net present cost for each alternative by the area between the PCI (Figure 17) and the minimum acceptable PCI during the analysis period (1980 to 2000). Table 6 shows the results of these computations. Although the differences are still narrow, alternatives B, D, and E appear to be more advantageous.

Based on the overall analysis, it is recommended that alternative D be adopted; i.e., recycle surface, reusing it as base, then add new 3-inch AC for the central 75 feet, and taper it to 1 inch at the edges. Alternative D is recommended, because it offers the following unique advantages:

1. It is the strongest alternative structurally of great importance in case of the heavy traffic operations.
2. It requires the least amount of future maintenance and thus less frequent traffic interruptions.
3. It will eliminate the possibility of reflection cracking by recycling the surface and using it as a base.
4. It provides an environmental advantage because of recycling.

It is recommended that alternative D be implemented within the coming 3 years (1981 to 1984).

It must be emphasized that any new AC mix should be carefully designed to minimize temperature cracking. Special attention should be given to the asphalt grade and specifications. Acceptance of the mix should be based on analysis similar to that described in the section on "Laboratory Investigation".

The asphalt selected should have a penetration of approximately 120 and percent penetration after the thin film oven test of 65-75. If no asphalt supplier in the area can meet the required specifications, then consideration should be given to reconstructing the runway with concrete. Concrete was not analyzed in detail, since the initial cost was estimated to be four times that of alternative D. However, if no asphalt supplier can meet the requirements to minimize cracking, then reconstruction with concrete may be economically justified based on the life cycle costs.




FIGURE 1: LAYOUT AND TYPICAL SECTIONS  
AMEDEE ARMY AIRFIELD

Figure 1. Layout and typical sections Amedee Army Airfield.

DATE OF SURVEY: 15 NOV 1979

W ——— DIRECTION OF SURVEY ———> E

N ↑





Figure 2. Division of runway into features.




{ N = TOTAL NO. OF UNITS IN FEATURE  
 R = NUMBER OF RANDOM UNITS SURVEYED  
 A = NUMBER OF ADDITIONAL UNITS SURVEYED  
 I = ID-NUMBER OF UNITS SURVEYED

SAMPLE UNITS IDENTIFICATION


FEATURE (S)




RN1, RS1




RN2, RS2




RC1



RC2



RC4



RC3

Figure 3. Division of features into sample units.






Figure 4. PCI of individual sample units for central, north, and south features.




**Figure 5.** Photograph of Sierra Army Depot, Amedee Runway, showing primary type of distress (temperature cracking).



**Figure 6.** Runway layout showing location of cuts.



(a) Pavement before cut showing 4-inch wide crack.



(b) Pavement after cut showing crack to extend through the full depth of the top AC surface.

**Figure 7.** Cut #1.



(a) Cut showing medium and low severity cracks.



(b) Bottom of pavement slab. Cracks were found to extend through the full depth of the top AC surface.

**Figure 8. Cut #2.**



(a) Pavement slab being carefully lifted after saw cutting.



(b) Top of slab showing 8-inch-long crack.

**Figure 9.** Cut #3.



(c) Bottom of slab showing 3-inch crack propagated to bottom.

Figure 9. (continued)




Figure 10. Tensile strength vs. temperature for AC surface top 1.5 inch.

1 PAV.SEC.NO. 1 SIERRA ARMY BASE

TIME OF LOADING ,SEC = 3600.000

		MONTH CODE			
JULY	AUG.	SEPT.	OCT.	NOV.	DEC.
1	2	3	4	5	6
JAN.	FEB.	MAR.	APR.	MAY.	JUNE
7	8	9	10	11	12

		AIR TEMPERATURE	
ANNUAL AVERAGE	,DEG.F	=	49.500
ANNUAL RANGE	,DEG.F	=	39.600
DAILY RANGE	,DEG.F	=	34.500

		FACTORS AFFECTING PAV. TEMP.	
ANNUAL AVE. SOLAR RAD.	,LANGLEYS	=	455.000
JULY AVE. SOLAR RAD.	,LANGLEYS	=	730.000
ANNUAL AVE. WIND VEL.	,MPH.	=	6.300
SURFACE ABSORPTIVITY		=	.950
DEPTH FOR CALCULATION	,IN.	=	0.000
MIX. CONDUCTIVITY	,BTU-FT-HR-F.	=	.700
MIX. SPECIFIC HEAT	,BTU-LB-F.	=	.220
MIX. DENSITY	,LB/FT3	=	140.200

		ASPHALT PROPERTIES	
ORIG. PENETRATION	,DNM-SSEC.	=	90.
PEN. TEST TEMP.	,DEG.F	=	77.
ORIG. SOFTENING POINT	,DEG.F	=	121.
THIN FILM OVEN TEST	,PCT.ORIG.PEN.	=	72.000

		MIXTURE PROPERTIES	
PCT. ASPHALT	,BY WT.OF AGG.	=	7.527
ASPH. SPECIFIC GRAV.		=	1.023
AGG. SPECIFIC GRAV.		=	2.660
MIX. AIR VOIDS	,PERCENT	=	6.200
AGG. VOL. CONCENTRATION	-CALCULATED	=	.810
COEF. OF CONTRACTION	TEMP(F)	ALPH(10**5)	
	-70.		1.000
	0.		1.200
	70.		1.400
	210.		1.800
COEF. OF VARIATION OF ALPH		=	.100
MAX. TEN. STRENGTH	,PSI	=	435.000
COEF. OF VARIATION OF MAX. STRENGTH		=	.200

INPUT FATIGUE DATA		
FATIGUE CURVE $N=A*(1.0/STRAIN)^B$		
MIX. STIF. (PSI)	CONST. A	CONST. B
.1000E+02	.1000E-01	.3000E+01
.3000E+07	.8000E-12	.3950E+01

1 PAV.SEC.NO. 1 SIERRA ARMY BASE

Figure 11. Data used in temperature cracking program.






Figure 12. Predicted cracking using temperature cracking program.

Facility: Sierra Army Runway Feature: RC3

1. Overall Condition Rating - PCI = 61  $\Rightarrow$  M4R Zone = Routine, Major, or Over 11  
Excellent, Very Good, Good, Fair, Poor, Very Poor, Failed.

2. Variation of Condition Within Feature - PCI

a. Localized Random Variation Yes No  
b. Systematic Variation: Yes No

3. Rate of Deterioration of Condition - PCI

a. Long-term period (since construction) Low Normal High  
b. Short-term period (1 year) unknown Low Normal High

4. Distress Evaluation

a. Cause

Load Associated Distress 56 percent deduct values  
Climate/Durability Associated 44 percent deduct values  
Other ( ) Associated Distress \_\_\_\_\_ percent deduct values

b. Moisture (Drainage) Effect on Distress Minor Moderate Major

5. Load-Carrying Capacity Deficiency No Yes

6. Surface Roughness Minor Moderate Major

7. Skid Resistance/Hydroplaning unknown (runways only)

a. Mu-Meter Transitional  
Potential for hydroplaning  
Very high probability

b. Stopping Distance Ratio No hydroplaning anticipated  
Potential not well defined  
Potential for hydroplaning  
Very high hydroplaning  
potential

c. Transverse Slope Poor Fair Good Excellent

8. Previous Maintenance Low Normal High

9. Effect on Mission (Comments): \* Pavement is structurally  
adequate. However, surface cracking causing 64%  
of total deduct is due to weakened areas adjacent  
to climate caused cracks.

Figure 13. Airfield pavement condition evaluation summary.








M & R ZONE	PCI		RATING
ROUTINE	100		EXCELLENT
	85		VERY GOOD
ROUTINE, MAJOR, OVERALL,	70		GOOD
	55		FAIR
MAJOR, OVERALL	40		POOR
OVERALL	25		VERY POOR
	10		FAILED
	0		

Figure 14. Correlation of M&R zones with PCI and condition rating.






Figure 15. Rate of deterioration of AC pavements (no overlays).



FLEXIBLE PAVEMENT EVALUATION CURVES, C-141, TYPE A TRAFFIC AREAS

Figure 16. Evaluation of load carrying capacity.





Figure 17. Expected PCI over time for each M&R alternative.




**Work Summary:** Continue to repair cracks as they appear or deteriorate.  
 Cracks less than 1 inch wide will be sealed. Cracks over  
 1 inch wide will be patched.

**Initial Cost**


- |   |             |
|---|-------------|
| 1. Seal cracks less than 1 inch wide<br>(See Est #1, Figure 19)   | = \$ 29,444 |
| 2. Patch cracks over 1 inch wide<br>(See Est #2, Figure 19)   | = \$ 21,609 |
| 3. Patch alligator and slippage cracking<br>(See Est #3, Figure 19)   | = \$ 5,361  |
| 4. Apply rejuvenator<br>( $\approx 0.1$ gal/SY, $\approx \$0.4$ /SY)<br>$6800 \times 150 \times 1/9 \times 0.4$ | = \$ 45,333 |

	Total Initial Cost    \$101,747
--	---------------------------------

**Figure 18.** Alternative A: continue crack seal to PCI=40 (1987), then overlay.



**Work Summary:** 1. Repair cracks (sealing & patching).  
2. Overlay with AC as shown below.



#### Initial Cost

1. Seal all cracks less than 1 inch wide. Narrow cracks should be routed and cleaned. A space backer should be inserted before filling the cracks with a sealer. Assume half the medium severity cracks are less than 1 inch wide.

Total length of cracks to be sealed  
=  $16588 + 1/2 (25712) = 29444\text{LF}$

Crack seal =  $29444 \times \$1.0/\text{LF}$  = \$ 29,444

2. Saw cut and patch cracks over 1 inch wide. The patch should be approximately 6 inches wide and 3 inches deep.

Quantity =  $1/2 (25712) + 8753 = 21609\text{LF}$

Crack patch =  $21609 \times \$1.0/\text{LF}$  = \$ 21,609

3. Patch alligator and slippage cracking with 3-inch AC  
( $248\text{SF} + 5051\text{SF} + 62\text{SF}$ )  $\times \$1.0/\text{SF}$

= \$ 5,361

4. Tack coat —  $\$1.0/\text{gal}$ , Apply  $0.1 \text{ gal}/\text{SY}$   
= @  $\$0.1/\text{SY}$

$6800 \times 150 \times 1/9 \times .1$  = \$ 11,333

5. New AC hot mix in place @  $\$45/\text{ton}$

$(6800 \times 150 \times 2/12) \times 142 \times 1/2000 \times 45$  = \$543,150


6. Apply rejuvenator, construction coat

( $\approx .075 \text{ gal}/\text{SY} \approx \$0.3/\text{SY}$ )

$6800 \times 150 \times 1/9 \times 0.3$  = \$ 34,000

**Total Initial Cost** \$644,897

**Figure 19. Alternative B: overlay 1980.**




**Work Summary:** 1. Cold mill surface and store on base for future use.  
2. Place new 3 inch hot AC.

**Initial Cost**


1. Cold mill AC surface @ \$0.75/SY/in.	
$6800 \times 150 \times 1/9 \times 3 \times 0.75$	= \$ 255,000
2. Hauling and stockpiling cold-milled material	
Assume 1-mile haul @ \$0.5/ton mile	
$6800 \times 150 \times 3/12 \times 142 \times 1/2000 \times 0.5$	= \$ 9,053
3. Prime base course \$1.0/gal, Apply 0.2 gal/SY	
$6800 \times 150 \times 1/9 \times 0.2 \times 1.0$	= \$ 22,667
4. New AC hot mix @ \$45.0/ton	
$6800 \times 150 \times 3/12 \times 142 \times 1/2000 \times 45$	= \$ 814,725
5. Apply rejuvenator, construction coat	
( $\approx .075$ gal/SY $\approx$ \$0.3/SY)	
$6800 \times 150 \times 1/9 \times .3$	= \$ 34,000
<b>Total Initial Cost</b>	<b>\$1,135,445</b>

**Figure 20.** Alternative C: replace surface — 3-inch deep.





- Work Summary:**
1. Cold mill 150 ft width.
  2. Recycle cold milled material and reuse as stabilized base.
  3. Place new AC hot mix as shown below.




**Initial Cost**

1. Cold milling @ \$0.75/SY/in.  
 $6800 \times 150 \times 1/9 \times 3 \times 0.75 = \$ 255,000$
2. Wind rowing mil. @ \$0.25/ton  
 $6800 \times 150 \times 3/12 \times 142 \times 1/2000 \times .25 = \$ 4,526$
3. Place cold-milled material as a base, compact & apply prime @ \$0.4/SY/in.  
 $6800 \times 150 \times 1/9 \times 0.4 \times 3 = \$ 136,000$
4. Place new AC hot mix as shown above @ \$45/ton  
 central 75:  $6800 \times 75 \times 3/12 \times 142 \times 1/2000 \times 45 = \$ 407,362$   
 outside:  $6800 \times 75 \times 2/12 \times 142 \times 1/2000 \times 45 = \$ 271,575$
5. Apply rejuvenator, construction coat  
 ( $\approx .075$  gal/ SY @  $\approx \$0.3$ /SY)  
 $6800 \times 150 \times 1/9 \times 0.3 = \$ 34,000$

---

**Total Initial Cost     \$1,108,463**

**Figure 21.** Alternative D: recycle surface and use as base, add new surface.



**Work Summary:** 1. Cold mill central 75 ft — 3 in. depth and store on base for future use.  
 2. Place new 3 in. AC in central 75 ft.  
 3. Maintain cracks in outside edges.

**Initial Cost**

1. Cold mill central 75 ft — 3 inch @ \$0.75/SY/in.	
$6800 \times 75 \times 1/9 \times 3 \times .75$	= \$127,500
2. Hauling and stockpiling cold-milled material assume 1 mile haul @ \$.05/ton mile	
$6800 \times 75 \times 3/12 \times 142 \times 1/2000 \times .5$	= \$ 4,526
3. Prime base course \$1.0/gal, Apply 0.2 gal/SY	
$6800 \times 75 \times 1/9 \times .2 \times 1.0$	= \$ 11,333
4. New AC hot mix @ \$45.0/ton	
$6800 \times 75 \times 3/12 \times 142 \times 1/2000 \times 45$	= \$407,362
5. Repair cracks outside central 75 ft 18906 LF of crack x \$1.0/LF (See Table 4)	= \$ 18,906
6. Apply rejuvenator, central 75 ft ( $\approx .075$ gal/SY @ $\approx$ \$0.3/SY)	
$6800 \times 75 \times 1/9 \times .3$	= \$ 17,000
7. Apply rejuvenator, outside 75 ft ( $\approx 0.1$ gal/SY @ $\approx$ \$0.4/SY)	
$6800 \times 75 \times 1/9 \times .4$	= \$ 22,666
<b>Total Initial Cost</b>	<b>\$609,293</b>

**Figure 22.** Alternative E: replace surface central 75 feet, crack seal outside.

REPORT DATE - 80/08/08.

COMPARISON OF M&R ALTERNATIVES  
SIERRA  
SECTION RU

ANALYSIS PERIOD - 20 YEARS

INFLATION RATE 10.00 PERCENT  
INTEREST RATE 10.00 PERCENT

ALTERNATIVE	DESCRIPTION	NET PRESENT COST
B	OVERLAY-1980	965563.
E	REPLACE SURFACE CENTRAL 75 FT, CRK SEAL OUTSIDE	1007500.
A	CONT CRK SEAL TO PCI=40(1987) THEN OVERLAY	1044139.
D	RECYCLE SURFACE AND USE AS BASE, ADD NEW SURFACE	1169796.
C	REPLACE SURFACE-3 INCH DEEP	1267111.

DETAILED COMPARISON OF M&R ALTERNATIVES

	ALT A	ALT B	ALT C	ALT D	ALT E
YEAR	PRES COST	PRES COST	PRES COST	PRES COST	PRES COST
0 (FY80)	101747	101747	644897	644897	1135445
1 (FY81)	0	0	0	0	0
2 (FY82)	41403	41402	10000	10000	0
3 (FY83)	0	0	0	0	0
4 (FY84)	43213	43212	20000	20000	0
5 (FY85)	0	0	0	0	0
6 (FY86)	83960	83960	30000	29999	0
7 (FY87)	588483	588482	0	0	0
8 (FY88)	0	0	75333	75333	46333
9 (FY89)	10000	9999	0	0	0
10 (FY90)	0	0	20000	20000	0
11 (FY91)	20000	20000	0	0	0
12 (FY92)	0	0	30000	29999	5000
13 (FY93)	30000	29999	0	0	0
14 (FY94)	0	0	30000	30000	10000
15 (FY95)	75333	75333	0	0	0
16 (FY96)	0	0	75333	75333	60333
17 (FY97)	20000	20000	0	0	0
18 (FY98)	0	0	30000	30000	10000
19 (FY99)	30000	30000	0	0	0
20 (FY00)	0	0	0	0	0
TOTAL	1044139	1044138	965563	965563	1267111
SALVAGE	0	0	0	0	0
PRES WORTH	1044138	965563	1267111	1169796	1007500

Figure 23. Life cycle costing of M&R alternatives.

**Table 1**  
**Summary of Linear Cracking for Entire Runway**

Feature ID	Low Sev.		Med. Sev.		High Sev.		Total Crk.	
	Quant. LF	Dens. %	Quant. LF	Dens. %	Quant. LF	Dens. %	Quant. LF	Dens. %
RN1	215	3.82	44	.78			259	4.6
RN2	1348	.54	6506	2.6	2473	.99	10327	4.13
RS1	37	.65					37	0.65
RS2	3274	1.31	2666	1.06	2343	0.93	8283	3.33
RC1	328	2.91	329	2.92			657	5.83
RC2	1571	2.46	1030	1.61	800	1.25	3401	5.32
RC3	7711	2.05	12762	3.4	3074	.81	23547	6.26
RC4	2104	3.50	2375	3.95	63	0.1	4542	7.55
Total Crk. & Overall Dens.	16588	1.63	25712	2.52	8753	0.86	51053	5.01

Low Severity Cracking, % of Total Cracking =  $(16588 / 51053) \times 100 = 32.5\%$

Med. Severity Cracking, % of Total Cracking =  $(25712 / 51053) \times 100 = 50.4\%$

High Severity Cracking, % of Total Cracking =  $(8753 / 51053) \times 100 = 17.1\%$

**Table 2**  
**Summary of Distresses Other Than Linear Cracking**

Feature ID	Distress Type	Low Sev.		Med. Sev.		High Sev.		Total Crk.	
		Quant.	Dens.	Quant.	Dens.	Quant.	Dens.	Quant.	Dens.
RC2	Slippage* Cracking							248SF	0.38
RC3	Alligator Cracking	348	.09	3681	0.98	1022	.27	5051SF	1.34
RC4	Alligator Cracking			62	0.1			62SF	.1

\*Slippage cracking has no severity levels.

**Table 3**  
**Predicted Cracks and Repair Costs for Entire Runway**

Age Years	Year	Total Cracks, LF	Cracks to be Sealed, LF	Cracks to be Resealed, LF	Cost of Crack Repair (@ \$1.0/LF)
11	80	51053	51053	0	51053
13	82	92456	41403	0	41403
15	84	135669	43213	0	43213
17	86	168576	32907	51053	83960
19	88	186863	18287	41403	59690
21	90	194291	7428	43213	50641
23	92	196498	2207	83960	86167
25	94	196971	473	59690	60163
27	96	197030	59	50641	50700
29	98	197050	20	86167	86187
31	00	197050	0	60163	60163

\$673,340

**Table 4**  
**Summary of Linear Cracking Outside the Central 75 Ft**

Feature ID	Low Sev.		Med. Sev.		High Sev.		Total Crk.	
	Quant. LF	Dens. %	Quant. LF	Dens. %	Quant. LF	Dens. %	Quant. LF	Dens. %
RN1	215	3.82	44	.78			259	4.6
RN2	1348	.54	6506	2.6	2473	.99	10327	4.13
RS1	37	.65					37	.65
RS2	3274	1.31	2666	1.06	2343	.93	8283	3.33
Total								
Crk. &	4874	0.96	9216	1.81	4816	0.94	18906	3.71
Overall								
Dens.								

Low Severity Cracking, % of Total Cracking = (4874/18906) = 25.8

Med. Severity Cracking, % of Total Cracking = (9216/18906) = 48.7

High Severity Cracking, % of Total Cracking = (4816/18906) = 25.5

**Table 5**  
**Predicted Cracks and Repair Cost for Outside the Central 75 Ft**

Age Years	Year	Total Cracks, LF	Cracks to be Sealed, LF	Cracks to be Resealed, LF	Cost of Crack Repair (@ \$1.0/LF)
11	80	18906	18906	0	18906
13	82	36379	17473	0	17473
15	84	57771	21392	0	21392
17	86	77867	20096	18906	39002
19	88	92381	14514	17473	31987
21	90	100438	8057	21392	29449
23	92	103861	3423	39002	42425
25	94	104977	1116	31987	33103
27	96	105262	285	29449	29734
29	98	105315	53	42425	42478
31	00	105325	10	33103	33113

\$339,062

**Table 6**  
**Comparison of S/Unit Performance for Each M&R Alternative**

Alternative	Net Present Cost	Area Between PCI & Min. PCI		S/Unit Performance
A	1,044,138	$(63 - 40) \times 7/2 +$ $(100 - 40) \times 13/2$	= 470.5	2219
B	965,563	$(100 - 40) \times 17/2 + 0$	= 510	1893
C	1,267,111	$(100 - 40) \times 18/2 + 0$	= 540	2346
D	1,169,796	$(100 - 40) \times 20/2$	= 600	1950
E*	1,007,500	$(100 - 40) \times 18/2$	= 540	1866

\*Only applicable to the central 75 ft.

APPENDIX A:  
PCI COMPUTER OUTPUT

0

-----

FEATURE IDENTIFICATION =      RN1 SIERRA AFB CA

DATE SURVEYED      11/14/79.      FLEXIBLE    PAVEMENT.

FEATURE SIZE =      00005625    SF

TOTAL NO OF SAMPLE UNIT =      1

ALLOWABLE ERROR WITH 95% CONFIDENCE =      5

SAMPLE UNIT ID =      1

AREA OF SAMPLE,SF =    5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	215	3.82	11.5
08	MEDIUM	44	0.78	10.0

PCI = 89

NO. OF RANDOM SAMPLE =      1

NO. OF ADDITIONAL SAMPLE =      0

PCI OF FEATURE -RN1 SIERRA AFB CA      = 89    RATING = EXCELLENT

RECOMMEND EVERY SAMPLE UNITS TO BE SURVEYED.

ESTIMATED DISTRESS FOR FEATURE = RN1 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	215	3.82	11.5
08	MEDIUM	44	0.78	10.0

0

0

FEATURE IDENTIFICATION = RM2 SIERRA AFB CA

DATE SURVEYED 11/14/79. FLEXIBLE PAVEMENT.

FEATURE SIZE = 00249375 SF

TOTAL NO OF SAMPLE UNIT = 45

ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 4  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	MEDIUM	170	3.02	19.8

PCI = 80

SAMPLE UNIT ID = 10  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	MEDIUM	150	2.66	18.5

PCI = 82

SAMPLE UNIT ID = 16  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	123	2.18	8.3
08	MEDIUM	96	1.70	15.0

PCI = 85

SAMPLE UNIT ID = 22  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	49	0.87	4.9
08	MEDIUM	110	1.95	16.0

PCI = 79

SAMPLE UNIT ID = 28  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	25	0.44	3.6
08	MEDIUM	113	2.00	16.3

PCI = 80



SAMPLE UNIT ID = 32 \*ADDITIONAL\*  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	110	1.95	7.8
08	MEDIUM	37	0.65	9.1
08	HIGH	47	0.83	18.3

PCI = 82

SAMPLE UNIT ID = 34  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	3	0.05	1.2
08	MEDIUM	138	2.45	17.8
08	HIGH	392	6.96	46.3

PCI = 54

SAMPLE UNIT ID = 40  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	MEDIUM	268	4.76	24.3

PCI = 76

NO. OF RANDOM SAMPLE = 7

NO. OF ADDITIONAL SAMPLE = 1

PCI OF FEATURE -RN2 SIERRA AFB CA = 77 RATING = V. GOOD

RECOMMENDED MINIMUM OF 17 RANDOM SAMPLE UNITS TO BE SURVEYED.

STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED= 10.3

ESTIMATED DISTRESS FOR FEATURE = RN2 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	1348	0.54	3.9
08	MEDIUM	6506	2.60	18.3
08	HIGH	2473	0.99	19.9

0

0

FEATURE IDENTIFICATION = RS1 SIERRA AFB CA  
DATE SURVEYED 11/14/79. FLEXIBLE PAVEMENT.  
FEATURE SIZE = 00005625 SF

TOTAL NO OF SAMPLE UNIT = 1  
ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 1  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	37	0.65	4.2

PCI = 96

NO. OF RANDOM SAMPLE = 1

NO. OF ADDITIONAL SAMPLE = 0

PCI OF FEATURE -RS1 SIERRA AFB CA = 96 RATING = EXCELLENT

RECOMMEND EVERY SAMPLE UNITS TO BE SURVEYED.

ESTIMATED DISTRESS FOR FEATURE = RS1 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	37	0.65	4.2

0

-----

0

FEATURE IDENTIFICATION = RS2 SIERRA AFB CA

DATE SURVEYED 11/14/79. FLEXIBLE PAVEMENT.

FEATURE SIZE = 00249375 SF

TOTAL NO OF SAMPLE UNIT = 45

ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 4

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	2	0.03	0.7
08	MEDIUM	6	0.10	4.0
08	HIGH	126	2.24	29.0

PCI = 66

SAMPLE UNIT ID = 10

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	26	0.46	3.7
08	HIGH	74	1.35	22.9

PCI = 73

SAMPLE UNIT ID = 16

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	73	1.29	6.0
08	MEDIUM	106	1.88	15.7

PCI = 84

SAMPLE UNIT ID = 22

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	196	3.48	10.9
08	MEDIUM	88	1.56	14.4
08	HIGH	38	0.67	16.6

PCI = 78

SAMPLE UNIT ID = 28  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	46	0.81	4.7
08	MEDIUM	37	0.65	9.1
08	HIGH	37	0.65	16.3

PCI = 83

SAMPLE UNIT ID = 34  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	3	0.05	1.2
08	MEDIUM	147	2.61	18.3
08	HIGH	55	0.97	19.7

PCI = 76

SAMPLE UNIT ID = 40  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	171	3.04	10.0
08	MEDIUM	37	0.65	9.1
08	HIGH	38	0.67	16.6

PCI = 82

NO. OF RANDOM SAMPLE = 7

NO. OF ADDITIONAL SAMPLE = 0

PCI OF FEATURE -RS2 SIERRA AFB CA = 77 RATING = V. GOOD

RECOMMENDED MINIMUM OF 9 RANDOM SAMPLE UNITS TO BE SURVEYED.

STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYEDZ 6.4

ESTIMATED DISTRESS FOR FEATURE = RS2 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	3274	1.31	6.1
08	MEDIUM	2666	1.06	11.8
08	HIGH	2343	0.93	19.3

0

0

FEATURE IDENTIFICATION = RC1 SIERRA AFB CA

DAT= SURVEYED 11/14/79. FLEXIBLE PAVEMENT.

FEATURE SIZE X 00011250 SF

TOTAL NO OF SAMPLE UNIT X 2

ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 1  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	183	3.25	10.4
08	MEDIUM	289	5.13	25.2

PCI = 75

SAMPLE UNIT ID = 2  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	145	2.57	9.1
08	MEDIUM	40	0.71	9.5

PCI = 91

NO. OF RANDOM SAMPLE = 2

NO. OF ADDITIONAL SAMPLE = 0

PCI OF FEATURE -RC1 SIERRA AFB CA = 83 RATING = V. GOOD

RECOMMEND EVERY SAMPLE UNITS TO BE SURVEYED.

ESTIMATED DISTRESS FOR FEATURE = RC1 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	328	2.91	9.8
08	MEDIUM	329	2.92	19.5

0

0

FEATURE IDENTIFICATION = RC2 SIERRA AFB CA

DATE SURVEYED 11/14/79. FLEXIBLE PAVEMENT.

FEATURE SIZE 2 00063750 SF

TOTAL NO OF SAMPLE UNIT 2 11

ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 1

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY 2	DEDUCT VALUE
08	LOW	363	6.45	16.9
08	MEDIUM	97	1.72	15.1

PCI = 81

SAMPLE UNIT ID = 3

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY 2	DEDUCT VALUE
08	LOW	95	1.68	7.0
08	MEDIUM	64	1.13	12.2
08	HIGH	88	1.56	24.6

PCI = 75

SAMPLE UNIT ID = 5

AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY 2	DEDUCT VALUE
08	LOW	145	2.57	9.1
08	MEDIUM	102	1.81	15.5
08	HIGH	30	0.53	14.8

PCI = 80

SAMPLE UNIT ID = 7  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	44	0.78	4.6
08	MEDIUM	93	1.65	14.8
08	HIGH	94	1.67	25.4

PCI = 71

SAMPLE UNIT ID = 9 \*ADDITIONAL\*  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	23	0.40	3.5
08	MEDIUM	114	2.02	16.3
08	HIGH	142	2.52	30.5
15		132	2.34	21.9

PCI = 56

SAMPLE UNIT ID = 11  
AREA OF SAMPLE,SF = 7500

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	152	2.02	8.0
08	MEDIUM	117	1.56	14.4
08	HIGH	128	1.70	25.6
15		60	0.80	10.5

PCI = 72

NO. OF RANDOM SAMPLE = 5

NO. OF ADDITIONAL SAMPLE = 1

PCI OF FEATURE -RC2 SIERRA AFB CA = 74 RATING = V. GOOD

RECOMMENDED MINIMUM OF 005 RANDOM SAMPLE UNITS TO BE SURVEYED.

STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYEDX 4.5

ESTIMATED DISTRESS FOR FEATURE = RC2 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	1571	2.46	8.9
08	MEDIUM	1030	1.61	14.6
08	HIGH	800	1.25	22.1
15		248	0.38	7.3

0

0

FEATURE IDENTIFICATION = RC3 SIERRA AFB CA

DATE SURVEYED 11/14/79. FLEXIBLE PAVEMENT.

FEATURE SIZE Z 00375000 SF

TOTAL NO OF SAMPLE UNIT Z 67

ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 6  
 AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	152	2.70	9.4
08	MEDIUM	78	1.38	13.5
08	HIGH	77	1.36	23.0

PCI = 75

SAMPLE UNIT ID = 13  
 AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	140	2.48	8.9
08	MEDIUM	74	1.31	13.1
08	HIGH	95	1.68	25.4

PCI = 74

SAMPLE UNIT ID = 20  
 AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY Z	DEDUCT VALUE
08	LOW	182	3.23	10.4
08	MEDIUM	206	3.66	21.5
08	HIGH	76	1.35	22.9
01	LOW	18	0.32	11.1
01	MEDIUM	225	4.00	44.0
01	HIGH	24	0.42	28.3

PCI = 33



SAMPLE UNIT ID = 27  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	55	0.97	5.3
08	MEDIUM	183	3.25	20.4
08	HIGH	76	1.35	22.9
01	MEDIUM	17	0.30	18.5
01	HIGH	3	0.05	8.0

PCI = 61

SAMPLE UNIT ID = 34  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	81	1.44	6.3
08	MEDIUM	271	4.81	24.5
08	HIGH	69	1.22	21.8
01	LOW	10	0.17	8.1
01	MEDIUM	5	0.08	8.0
01	HIGH	45	0.80	34.3

PCI = 47

SAMPLE UNIT ID = 41  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	150	2.66	9.3
08	MEDIUM	182	3.23	20.3
08	HIGH	10	0.17	9.0

PCI = 80

SAMPLE UNIT ID = 48  
AREA OF SAMPLE,SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	57	1.01	5.5
08	MEDIUM	174	3.09	20.0
01	MEDIUM	240	4.26	44.7

PCI = 55

SAMPLE UNIT ID = 55  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	182	3.23	10.4
08	MEDIUM	262	4.65	24.0
01	LOW	19	0.33	11.3
01	MEDIUM	10	0.17	13.8
01	HIGH	66	1.17	38.5

PCI = 49

SAMPLE UNIT ID = 62  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
08	LOW	42	0.74	4.4
08	MEDIUM	293	5.20	25.4
08	HIGH	12	0.21	10.0

PCI = 75

NO. OF RANDOM SAMPLE = 9

NO. OF ADDITIONAL SAMPLE = 0

PCI OF FEATURE -RC3 SIERRA AFB CA = 61 RATING = GOOD

RECOMMENDED MINIMUM OF 31 RANDOM SAMPLE UNITS TO BE SURVEYED.

STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYEDX 16.1

ESTIMATED DISTRESS FOR FEATURE = RC3 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY %	DEDUCT VALUE
01	LOW	348	0.09	6.3
01	MEDIUM	3681	0.98	29.2
01	HIGH	1022	0.27	24.2
08	LOW	7711	2.05	8.1
08	MEDIUM	12762	3.40	20.8
08	HIGH	3074	0.81	18.1

0

0

FEATURE IDENTIFICATION = RC4 SIERRA AFB CA

DATE SURVEYED 11/15/79. FLEXIBLE PAVEMENT.

FEATURE SIZE X 00060000 SF

TOTAL NO OF SAMPLE UNIT X 11

ALLOWABLE ERROR WITH 95% CONFIDENCE = 5

SAMPLE UNIT ID = 1  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	120	2.13	8.2
08	MEDIUM	219	3.89	22.1
01	MEDIUM	12	0.21	15.4

PCI = 75

SAMPLE UNIT ID = 3  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	233	4.14	12.1
08	MEDIUM	291	5.17	25.3
01	MEDIUM	35	0.62	24.8

PCI = 63

SAMPLE UNIT ID = 5  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	221	3.92	11.7
08	MEDIUM	157	2.79	19.0

PCI = 81

SAMPLE UNIT ID = 7  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	45	1.15	5.8
08	MEDIUM	190	3.37	20.7
08	HIGH	63	1.12	21.0
01	MEDIUM	15	0.26	17.3

PCI = 68

SAMPLE UNIT ID = 9  
AREA OF SAMPLE, SF = 5625

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
08	LOW	219	3.89	11.6
08	MEDIUM	280	4.97	24.9

PCI = 75

NO. OF RANDOM SAMPLE = 5

NO. OF ADDITIONAL SAMPLE = 0

PCI OF FEATURE -RC4 SIERRA AFB CA = 72 RATING = V. GOOD

RECOMMENDED MINIMUM OF 7 RANDOM SAMPLE UNITS TO BE SURVEYED.

STANDARD DEVIATION OF PCI BETWEEN RANDOM UNITS SURVEYED 6.9

ESTIMATED DISTRESS FOR FEATURE = RC4 SIERRA AFB CA

DISTRESS-TYPE	SEVERITY	QUANTITY	DENSITY X	DEDUCT VALUE
01	MEDIUM	132	0.22	15.8
08	LOW	1830	3.05	10.0
08	MEDIUM	2425	4.04	22.5
08	HIGH	134	0.22	10.2

1	FEATURE	PCI	RATING
	RC3 SIERRA AFB CA	61	GOOD
	RC4 SIERRA AFB CA	72	V. GOOD
	RC2 SIERRA AFB CA	74	V. GOOD
	RN2 SIERRA AFB CA	77	V. GOOD
	RS2 SIERRA AFB CA	77	V. GOOD
	RC1 SIERRA AFB CA	83	V. GOOD
	RN1 SIERRA AFB CA	89	EXCELLENT
	RS1 SIERRA AFB CA	96	EXCELLENT

EOI ENCOUNTERED.

C>

**APPENDIX B:  
RESULTS OF AC LABORATORY TESTING**

**Table B1  
Bituminous Mix Analysis**

PROJECT Sierra Army Depot JOB NO. \_\_\_\_\_ DATE 20 May 1980  
SOURCE \_\_\_\_\_ SAMPLED BY \_\_\_\_\_ DATE REC'D \_\_\_\_\_  
DESCRIPTION OF MATERIALS Asphalt Cement Slabs

LABORATORY NO. <u>FPL 5864</u>					
FIELD NO. _____					
OTHER IDENTIFICATION		Top Layer		Bottom Layer	
PAVEMENT CRITERION ( ) PSI TIRE PRESSURE		Laboratory Samples*		Laboratory Samples*	
SIZE OF SIEVE	SPECIFIED LIMITS	JOB MIX FORMULA (APPROVED)	Field Samples	Field Samples	Field Samples
1 INCH					
3/4 INCH			100.0		100.0
1/2 INCH			94.3		93.7
3/8 INCH			85.2		82.6
NO. 4			71.6		63.8
NO. 8			56.6		48.2
NO. 16			41.0		35.2
NO. 30			30.1		26.2
NO. 50			21.6		19.0
NO. 100			14.3		12.6
NO. 200			8.6		7.6
PERCENT BITUMEN			7.0	7.0	5.5
GRADE BITUMEN			--		--
STABILITY (MARSHALL) LBS			5466		5153
FLOW 0.01 INCHES			16		17
PERCENT VOIDS TOTAL MIX			4.9	6.2	8.9
PERCENT VOIDS FILLED			75.8	70.6	57.3
DENSITY - LBS/CU FT			142.4	140.2	140.6
THEO DENSITY - LBS/CU FT			149.7		154.3
STRIPPING, %			--		--
SWELL, %			--		--
AGG - SP GR			2.66		2.69
AGG - % WATER ABSORPTION			1.6		2.0

REMARKS:

Test on Recovered Asphalt

Penetration		15	13
Softening Pt. °C		71.2°C	75.0°C
Viscosity	Poises	140°F	268,884
	CST	225°F	27,535
	CST	275°F	3,451

TESTED BY: \_\_\_\_\_

CHECKED BY: \_\_\_\_\_

WES FORM NO. 1008  
REV MARCH 1968

\*Gyratory compaction at 200 psi, one degree, and 30 revolutions which is equivalent to 75 blows Marshall compaction effort

**Table B2**  
**Indirect Tensile Results**

Sample No.	Maximum Load (lb)	Vertical Deformation (in.)	Temp (°F)	Load Rate (in./min)
1-1 top	1950	0.080	75	2.0
1-1 bottom	2400	0.095	75	2.0
1-2 top	2550	0.055	50	2.0
1-2 bottom	3000	0.048	50	2.0
1-3 top	2800	0.045	20	2.0
1-3 bottom	2200	0.065	20	2.0
2-1 top	1025	0.095	75	0.05
2-1 bottom	900	0.120	75	0.05
2-2 top	2470	0.080	50	0.05
2-2 bottom	1990	0.065	50	0.05
2-3 top	3650	0.055	20	0.05
2-3 bottom	3450	0.042	20	0.05
Additional top	4020	0.042	-20°F	0.05
Additional bottom	4025	0.040	-20°F	0.05

**Table B3**  
**Sample Size**

Sample No.	Average Height (in.)	Average Diameter (in.)
Top 1-1	1.064	3.951
1-2	1.066	3.957
1-3	1.690	3.960
Top 2-1	1.485	3.960
2-2	1.587	3.966
2-3	1.587	3.955
Bottom 1-1	1.462	3.959
1-2	1.460	3.962
1-3	1.491	3.959
Bottom 2-1	1.601	3.962
2-2	1.561	3.949
2-3	1.577	3.957
Top-Additional	1.665	3.938
Bottom-Additional	1.723	3.917

**Table B4**  
**Computation of**  
**Indirect Tensile Strength**

Rate 2 in./min.

$$S = \frac{2P}{\pi \ell d}$$

Temp	Sample ID	$\ell$	d	P, lbs	S, Psi
75°F	Top 1-1	1.064	3.951	1950	295.30
50°F	Top 1-2	1.066	3.957	2550	384.86
20°F	Top 1-3	1.69	3.96	2800	266.352
75°F	Bottom 1-1	1.462	3.959	2400	263.93
50°F	Bottom 1-2	1.460	3.962	3000	330.17
20°F	Bottom 1-3	1.491	3.959	2200	237.27

Rate .05 in./min.

Temp	Sample ID	$\ell$	d	P, lbs	S
75°F	Top 2-1	1.485	3.96	1025	110.96
50°F	Top 2-2	1.587	3.966	2470	249.83
20°F	Top 2-3	1.587	3.955	3650	370.2
-20°F	Top-additional	1.665	3.938	4020	390.32
75°F	Bottom 2-1	1.601	3.962	900	90.33
50°F	Bottom 2-2	1.561	3.949	1990	205.52
20°F	Bottom 2-3	1.577	3.957	3450	351.97
-20°F	Bottom-additional	1.723	3.917	4025	379.67



**APPENDIX C:  
PROGRAM OUTPUT OF  
PCI PREDICTION FOR EACH  
M&R ALTERNATIVE**

**Alternative A. Overlay in 1987 — 2 inch average thickness.**

**SIERRA**

**C141 AIRCRAFT ID**  
**0.0 AGE BETWEEN ORIGINAL CONSTRUCTION AND LAST OVERLAY**  
**3.0 TOTAL AC THICKNESS IN INCHES INCLUDING OVERLAYS**  
**15.0 TOTAL PAVEMENT THICKNESS ABOVE SUBGRADE**  
**80.0 CBR OF BASE**  
**25.0 CBR OF SUBGRADE**  
  
**18.0 YEARS TO OVERLAY FROM LAST CONST/OVERLAY**  
**2.0 THICKNESS OF OVERLAY**

<b>AGE SINCE OVERLAY</b>	<b>PCI</b>
-----	---
0.0	100.0
5.0	77.2
10.0	54.4
13.0	40.8

**Alternative B. Overlay 1980 — 2-inch AC average thickness.**

**SIERRA**

**C141 AIRCRAFT ID**  
**0.0 AGE BETWEEN ORIGINAL CONSTRUCTION AND LAST OVERLAY**  
**3.0 TOTAL AC THICKNESS IN INCHES INCLUDING OVERLAYS**  
**15.0 TOTAL PAVEMENT THICKNESS ABOVE SUBGRADE**  
**80.0 CBR OF BASE**  
**25.0 CBR OF SUBGRADE**  
  
**11.0 YEARS TO OVERLAY FROM LAST CONST/OVERLAY**  
**2.0 THICKNESS OF OVERLAY**

<b>AGE SINCE OVERLAY</b>	<b>PCI</b>
-----	---
0.0	100.0
5.0	82.2
10.0	64.5
15.0	46.7
20.0	28.9

Alternatives C & E. Replace entire surface.

**SIERRA**

**C141 AIRCRAFT ID**

**0.0 AGE BETWEEN ORIGINAL CONSTRUCTION AND LAST OVERLAY**

**3.0 TOTAL AC THICKNESS IN INCHES INCLUDING OVERLAYS**

**15.0 TOTAL PAVEMENT THICKNESS ABOVE SUBGRADE**

**80.0 CBR OF BASE**

**25.0 CBR OF SUBGRADE**

<b>AGE SINCE LAST CONST/OVERLAY</b>	<b>PCI</b>
-----	---
0.0	100.0
5.0	83.3
11.0	63.3
20.0	33.4
25.0	16.7
31.0	0.0

Alternative D. Reuse surface as base and add new 3 inch AC.

**SIERRA**

**C141 AIRCRAFT ID**

**0.0 AGE BETWEEN ORIGINAL CONSTRUCTION AND LAST OVERLAY**

**3.0 TOTAL AC THICKNESS IN INCHES INCLUDING OVERLAYS**

**18.0 TOTAL PAVEMENT THICKNESS ABOVE SUBGRADE**

**100.0 CBR OF BASE**

**25.0 CBR OF SUBGRADE**

<b>AGE SINCE LAST CONST/OVERLAY</b>	<b>PCI</b>
-----	---
0.0	100.0
5.0	85.0
10.0	70.0
15.0	54.9
20.0	39.9

**APPENDIX D:  
PROGRAM OUTPUTS FOR  
PREDICTING FUTURE CRACKING**

**DISTRESS INPUT DATA**

DISTRESS TYPE = 8.  
AGE = 11.00 YEARS  
L = 8.43  
M = 13.03  
H = 4.45  
EARLIEST DISTRESS STARTING TIME = 0.0 YEARS  
LATEST DISTRESS STARTING TIME = 10.0 YEARS  
DISTRESS AT INITIAL TIME = .0100  
EARLIEST TIME FROM L TO M = 0.0 YEARS  
LATEST TIME FROM L TO M = 6.0 YEARS  
EARLIEST TIME FROM M TO H = 0.0 YEARS  
LATEST TIME FROM M TO H = 6.0 YEARS  
MAXIMUM PREDICTION AGE = 30.0 YEARS

**OPTIMUM VALUES**

INITIAL TIME = 0.0 YEARS  
TIME FROM L TO M = 1 YEARS  
TIME FROM M TO H = 3 YEARS  
MEAN = 13.2719 YEARS  
STANDARD DEVIATION = 3.5150 YEARS

YEAR	L+M+H	L	M	H
0	.01	.01	0.00	0.00
1	.03	.02	.01	0.00
2	.07	.04	.03	0.00
3	.18	.11	.07	0.00
4	.42	.24	.17	.01
5	.93	.51	.39	.03
6	1.93	1.00	.86	.07
7	3.72	1.79	1.76	.18
8	6.69	2.97	3.30	.42
9	11.22	4.53	5.76	.93
10	17.60	6.38	9.29	1.93
11	25.91	8.30	13.88	3.72
12	35.88	9.97	19.22	6.69
13	46.92	11.04	24.66	11.22
14	58.20	11.28	29.32	17.60
15	68.85	10.65	32.29	25.91
16	78.11	9.26	32.97	35.88
17	85.55	7.44	31.19	46.92
18	91.06	5.51	27.35	58.20
19	94.83	3.77	22.22	68.85
20	97.21	2.38	16.73	78.11
21	98.60	1.39	11.67	85.55
22	99.35	.75	7.34	91.06
23	99.72	.37	4.51	94.83
24	99.88	.17	2.50	97.21
25	99.96	.07	1.28	98.60
26	99.98	.03	.61	99.35
27	99.99	.01	.27	99.72
28	100.00	.00	.11	99.88
29	100.00	.00	.04	99.96
30	100.00	.00	.01	99.98

**CRACK PREDICTION FOR ENTIRE RUNWAY WIDTH  
(NOTE 100% = 197050 LINEAR FEET OF CRK)**

# DISTRESS INPUT DATA

DISTRESS TYPE = 8.  
 AGE = 11.00 YEARS  
 L = 4.63  
 M = 8.75  
 N = 4.57  
 EARLIEST DISTRESS STARTING TIME = 0.0 YEARS  
 LATEST DISTRESS STARTING TIME = 9.0 YEARS  
 DISTRESS AT INITIAL TIME = .0100  
 EARLIEST TIME FROM L TO M = 0.0 YEARS  
 LATEST TIME FROM L TO M = 6.0 YEARS  
 EARLIEST TIME FROM M TO N = 0.0 YEARS  
 LATEST TIME FROM M TO N = 6.0 YEARS  
 MAXIMUM PREDICTION AGE = 30.0 YEARS

## OPTIMUM VALUES

INITIAL TIME = 0.0 YEARS  
 TIME FROM L TO M = 1 YEARS  
 TIME FROM M TO N = 2 YEARS  
 MEAN = 14.5310 YEARS  
 STANDARD DEVIATION = 3.8494 YEARS

YEAR	L+M+N	L	M	N
0	.01	.01	0.00	0.00
1	.02	.01	.01	0.00
2	.06	.03	.02	0.00
3	.14	.08	.05	.01
4	.31	.17	.11	.02
5	.67	.35	.25	.06
6	1.34	.67	.53	.14
7	2.52	1.19	1.02	.31
8	4.49	1.97	1.86	.67
9	7.54	3.05	3.15	1.34
10	11.96	4.42	5.02	2.52
11	17.95	5.99	7.47	4.49
12	25.54	7.59	10.41	7.54
13	34.54	9.00	13.58	11.96
14	44.52	9.97	16.59	17.95
15	54.85	10.33	18.97	25.54
16	64.86	10.01	20.30	34.54
17	73.93	9.07	20.35	44.52
18	81.62	7.69	19.09	54.85
19	87.71	6.09	16.76	64.86
20	92.23	4.51	13.78	73.93
21	95.36	3.13	10.61	81.62
22	97.38	2.03	7.64	87.71
23	98.61	1.23	5.15	92.23
24	99.30	.70	3.25	95.36
25	99.67	.37	1.92	97.38
26	99.85	.18	1.06	98.61
27	99.94	.08	.55	99.30
28	99.97	.04	.27	99.67
29	99.99	.01	.12	99.85
30	100.00	.01	.05	99.94

CRACK PREDICTION FOR OUTSIDE 75 FEET ONLY  
 (NOTE 100% = 105325 LINEAR FEET OF CRK)

**APPENDIX E:  
FUTURE M&R COSTS  
FOR EACH M&R ALTERNATIVE**

(A)

**M & R ALTERNATIVE** CONTINUE CRACK SEALING AND  
PATCHING TO A PCI = 40 (1987) THEN OVERLAY

**ANALYSIS PERIOD** 20 **YEARS** **INTEREST RATE** \_\_\_\_\_ %

**INFLATION RATE** \_\_\_\_\_ %

YEAR	M&R WORK DESCRIPTION	COST \$	f	PRESENT WORTH \$
80	SEAL & PATCH CRACKS	51,053		
80	PATCH ALLIGATOR CRACKING	5,361		
80	APPLY REJUVENATOR	45,333		
82	SEAL & PATCH CRACKS	41,403		
84	SEAL & PATCH CRACKS	43,213		
86	SEAL & PATCH CRACKS	83,960		
87	TACK COAT	11,333		
87	OVERLAY	543,150		
87	APPLY REJ. CONST. COAT	34,000		
89	SEAL & PATCH CRACKS	10,000 *		
91	SEAL & PATCH CRACKS	20,000 *		
93	SEAL & PATCH CRACKS	30,000 *		
95	SEAL & PATCH CRACKS	30,000 *		
95	APPLY REJUVENATOR	45,333		
97	SEAL & PATCH CRACKS	20,000 *		
99	SEAL & PATCH CRACKS	30,000 *		

**TOTAL** \$

**SALVAGE VALUE =** \_\_\_\_\_ = \$ \_\_\_\_\_

**PRESENT WORTH =** \$ \_\_\_\_\_

\*ESTIMATED ASSUMING REFLECTION CRACKING

M & R ALTERNATIVE OVERLAY IN 1980 -- KEACH

PCI = 40 (ABOUT 1996)

ANALYSIS PERIOD 20 YEARS INTEREST RATE 8 %

**INFLATION RATE\_\_\_\_\_%**

**\*ESTIMATED ASSUMING REFLECTION CRACKING**

M & R ALTERNATIVE REPLACE SURFACE COURSE (3 INCH)

ANALYSIS PERIOD 20 YEARS INTEREST RATE        %

**INFLATION RATE\_\_\_\_\_%**

# ESTIMATED ASSUMING REFLECTION CRACKING.



M & R ALTERNATIVE RECYCLE SURFACE AND USE  
AS BASE - ADD NEW SURFACE

ANALYSIS PERIOD 20 YEARS INTEREST RATE      %

INFLATION RATE \_\_\_\_\_%

\* ESTIMATED ASSUMING REFLECTION CRACKING

(E)

**M & R ALTERNATIVE REPLACE KEEL (75 FT.) AND  
CONTINUE PATCH OUTSIDE 75 FT.**

**ANALYSIS PERIOD 20 YEARS INTEREST RATE \_\_\_\_\_ %**

**INFLATION RATE \_\_\_\_\_ %**

YEAR	M&R WORK DESCRIPTION	COST \$	f	PRESENT WORTH \$
80	COLD MILL 75 FT.	127,500		
80	HAULING MILLED MAT'L.	4,526		
80	PRIME BASE	11,333		
80	NEW AC SURFACE	407,362		
80	SEAL & PATCH OUTSIDE CRKS	18,906		
80	APPLY REJ. CONST. COAT (75')	22,666		
80	APPLY REJ. OUTSIDE	17,000		
88	SEAL & PATCH CRACKS	500 *		
88	APPLY REJUVENATOR	22,666		
92	SEAL & PATCH CRACKS	2,500 *		
94	SEAL & PATCH CRACKS	5,000 *		
96	SEAL & PATCH CRACKS	7,500 *		
96	APPLY REJUVENATOR	22,666		
98	SEAL & PATCH CRACKS	5,000 *		
82	SEAL & PATCH CRACKS	17,473		
84	SEAL & PATCH CRACKS	21,392		
86	SEAL & PATCH CRACKS	39,002		
88	SEAL & PATCH CRACKS	31,987		
88	APPLY REJUVENATOR	22,666		
90	SEAL & PATCH CRACKS	29,449		
92	SEAL & PATCH CRACKS	42,425		
94	SEAL & PATCH CRACKS	33,103		
96	SEAL & PATCH CRACKS	29,734		
96	APPLY REJUVENATOR	22,666		
98	SEAL & PATCH CRACKS	42,478 TOTAL		\$

**SALVAGE VALUE = \$ \_\_\_\_\_**

**PRESENT WORTH = \$ \_\_\_\_\_**

\* ESTIMATED ASSUMING REFLECTION CRACKING

# CERL DISTRIBUTION

Chief of Engineers  
ATTN: Tech Monitor  
ATTN: DAEN-ASL-L (2)  
ATTN: DAEN-CCP  
ATTN: DAEN-CW  
ATTN: DAEN-CWE  
ATTN: DAEN-CWH-R  
ATTN: DAEN-CWQ  
ATTN: DAEN-CWP  
ATTN: DAEN-MP  
ATTN: DAEN-MPC  
ATTN: DAEN-MPE  
ATTN: DAEN-MPO  
ATTN: DAEN-MPR-A  
ATTN: DAEN-RD  
ATTN: DAEN-ROC  
ATTN: DAEN-RDM  
ATTN: DAEN-RM  
ATTN: DAEN-ZC  
ATTN: DAEN-ZCE  
ATTN: DAEN-ZCI  
ATTN: DAEN-ZCM

## US Army Engineer Districts

ATTN: Library  
Alaska  
Al Batin  
Albuquerque  
Baltimore  
Buffalo  
Charleston  
Chicago  
Detroit  
Far East  
Fort Worth  
Galveston  
Huntington  
Jacksonville  
Japan  
Kansas City  
Little Rock  
Los Angeles  
Louisville  
Memphis  
Mobile  
Nashville  
New Orleans  
New York  
Norfolk  
Omaha  
Philadelphia  
Pittsburgh  
Portland  
Riyadh  
Rock Island  
Sacramento  
San Francisco  
Savannah  
Seattle  
St. Louis  
St. Paul  
Tulsa  
Vicksburg  
Walla Walla  
Wilmington

## US Army Engineer Divisions

ATTN: Library  
Europe  
Huntsville  
Lower Mississippi Valley  
Middle East  
Middle East (Rear)  
Missouri River  
New England  
North Atlantic  
North Central  
North Pacific  
Ohio River  
Pacific Ocean  
South Atlantic  
South Pacific  
Southwestern

Waterways Experiment Station  
ATTN: Library

Cold Regions Research Engineering Lab  
ATTN: Library

US Government Printing Office  
Receiving Section/Depository Copies (2)

Defense Technical Information Center  
ATTN: DDA (12)

Engineering Societies Library  
New York, NY

FESA, ATTN: Library

ETL, ATTN: Library

Engr. Studies Center, ATTN: Library

Inst. for Water Res., ATTN: Library

Army Instl. and Major Activities (CONUS)  
DARCOM - Dir., Inst., & Svcs.  
ATTN: Facilities Engineer  
ARRADCOM  
Aberdeen Proving Ground  
Army Matls. and Mechanics Res. Ctr.  
Corpus Christi Army Depot  
Harry Diamond Laboratories  
Dugway Proving Ground  
Jefferson Proving Ground  
Fort Marmouth  
Letterkenny Army Depot  
Natick Research and Dev. Ctr.  
New Cumberland Army Depot  
Pueblo Army Depot  
Red River Army Depot  
Redstone Arsenal  
Rock Island Arsenal  
Savanna Army Depot  
Sharpe Army Depot  
Seneca Army Depot  
Tobyhanna Army Depot  
Tooele Army Depot  
Watervliet Arsenal  
Yuma Proving Ground  
White Sands Missile Range

## FORSCOM

FORSCOM Engineer, ATTN: AFEN-FE  
ATTN: Facilities Engineers  
Fort Buchanan  
Fort Bragg  
Fort Campbell  
Fort Carson  
Fort Devens  
Fort Drum  
Fort Hood  
Fort Indiantown Gap  
Fort Irwin  
Fort Sam Houston  
Fort Lewis  
Fort McCoy  
Fort McPherson  
Fort George G. Meade  
Fort Ord  
Fort Polk  
Fort Richardson  
Fort Riley  
Presidio of San Francisco  
Fort Sheridan  
Fort Stewart  
Fort Walneright  
Vancouver Bks.

## TRADOC

HQ, TRADOC, ATTN: ATEN-FE  
ATTN: Facilities Engineer  
Fort Belvoir  
Fort Benning  
Fort Bliss  
Carlisle Barracks  
Fort Chaffee  
Fort Dix  
Fort Eustis  
Fort Gordon  
Fort Hamilton  
Fort Benjamin Harrison  
Fort Jackson  
Fort Knox  
Fort Leavenworth  
Fort Lee  
Fort McClellan  
Fort Monroe  
Fort Rucker  
Fort Sill  
Fort Leonard Wood

INSCOM - Ch, Instl. Div.  
ATTN: Facilities Engineer  
Vint Hill Farms Station  
Arlington Hall Station

WESTCOM  
ATTN: Facilities Engineer  
Fort Shafter

## MDW

ATTN: Facilities Engineer  
Cameron Station  
Fort Lesley J. McNair  
Fort Myer

## MSC

HQ USAHSC, ATTN: HSLD-F  
ATTN: Facilities Engineer  
Fitzsimons Army Medical Center  
Walter Reed Army Medical Center

## USACC

ATTN: Facilities Engineer  
Fort Huachuca  
Fort Ritchie

## MTMC

HQ, ATTN: MTMC-SA  
ATTN: Facilities Engineer  
Oakland Army Base  
Bayonne MOT  
Sunny Point MOT

## US Military Academy

ATTN: Facilities Engineer  
ATTN: Dept of Geography & Computer Science

## USAES, Fort Belvoir, VA

ATTN: ATZA-DTE-EM  
ATTN: ATZA-DTE-SU  
ATTN: Engr. Library

Chief Inst. Div., I&SA, Rock Island.

USA ARRCOM, ATTN: Dir., Instl & Svc  
TARCOM, Fac. Div.  
TECOM, ATTN: DRSTE-LG-F  
TSARCOM, ATTN: STSAS-F  
MARAD COM, ATTN: DRONA-F  
AMORC, ATTN: DRXMR-ME

HQ, XVIII Airborne Corps and  
Ft. Bragg  
ATTN: AFZA-FE-EE

HQ, 7th Army Training Command  
ATTN: AETTG-DEM (5)

HQ USAEUR and 7th Army  
ODCS/Engineer  
ATTN: AEAEN-EH (4)

V Corps  
ATTN: AETVDEN (5)

VII Corps  
ATTN: AETSDEH (5)

21st Support Command  
ATTN: AEREM (5)

US Army Berlin  
ATTN: ABEA-EN (2)

US Army Southern European Task Force  
ATTN: AESE-ENG (5)

US Army Installation Support Activity  
Europe  
ATTN: AEUES-RP

8th USA, Korea  
ATTN: EAPE  
Cdr, Fac Engr Act (8)  
AFE, Yongsoo Area  
AFE, 2D Inf Div  
AFE, Area II Spt Det  
AFE, Cp Humphreys  
AFE, Pusan  
AFE, Taegu

DLA ATTN: DLA-WI

USA Japan (USARJ)  
Ch, FE Div, AJEN-FE  
Fac Engr (Monstu)  
Fac Engr (Okineue)

ROK/US Combined Forces Command  
ATTN: EUSA-HMC-CFC/Engr

416th Engineer Command  
ATTN: Facilities Engineering

Horton AFB  
ATTN: AFCE-HR/DEE

MC Team Distribution

USA ARADCOM  
ATTN: ORDAR-LCA-OK

Director of Facilities Engineering  
Ft. Richardson, AK 99505  
Miami, FL 34004

USA Liaison Detachment  
ATTN: Library  
New York, NY 10007

West Point, NY 10996  
ATTN: Dept of Mechanics  
ATTN: Library

HQDA (SGPD-EDE)

Chief of Engineers  
ATTN: DAEN-MPO-B  
ATTN: DAEN-MPZ-A  
ATTN: DAEN-MPR (2)  
ATTN: DAEN-RDL  
ATTN: DAEN-ZCP

National Defense Headquarters  
Director General of Construction  
Ottawa, Ontario, Canada K1A 0K2

Division of Building Research  
National Research Council  
Ottawa, Ontario, Canada K1A 0R6

Airports and Const Services Dir  
Technical Info Reference Center  
Ottawa, Ontario, Canada K1A 0N8

Ft. Belvoir, VA 22060  
ATTN: ATSE-TD-TL (2)  
ATTN: Learning Resource Center  
ATTN: Kingman Bldg, Library  
ATTN: Canadian Liaison Officer (2)  
ATTN: British Liaison Officer (5)

US Army Foreign Science and  
Tech Center  
ATTN: Charlottesville, VA 22901  
ATTN: Far East Office

Ft. Leavenworth, KS 66027  
ATTN: ATZLCA-SA

Ft. Monroe, VA 23651  
ATTN: ATEN-AD (3)  
ATTN: ATEN-FE-ME  
ATTN: ATEN-FE-BG (2)

Ft. McPherson, GA 30330  
ATTN: AFEN-CD

Ft. Lee, VA 23801  
ATTN: DRXMC-D (2)

USA-WES  
ATTN: C/Structures  
ATTN: Soils & Pavements Lab

6th US Army  
ATTN: AFKC-EN

7th US Army  
ATTN: AETTM-HRD-EMD

HQ, Combined Field Army (ROK/US)  
ATTN: CFAR-EN  
APO San Francisco 96358

US Army Engineer District  
New York  
ATTN: Chief, Design Br.  
Pittsburgh  
ATTN: Chief, ORPCD  
ATTN: Chief, Engr Div  
Philadelphia  
ATTN: Chief, NAPEN-D

US Army Engineer District  
Baltimore  
ATTN: Chief, Engr Div  
Norfolk  
ATTN: Chief, NAOEN-M  
ATTN: Chief, NAOEN-D  
Huntington  
ATTN: Chief, ORHED-F  
Wilmington  
ATTN: Chief, SAWCO-C  
ATTN: Chief, SAWEN-D  
Charleston  
ATTN: Chief, Engr Div  
Savannah  
ATTN: Chief, SASAS-L  
Jacksonville  
ATTN: Const Div  
Mobile  
ATTN: Chief, SAMEN-D  
ATTN: Chief, SAMEN-F  
ATTN: Chief, SAMEN  
Nashville  
ATTN: Chief, ORNED-F  
Memphis  
ATTN: Chief, Const Div  
ATTN: Chief, LMMED-D  
Vicksburg  
ATTN: Chief, Engr Div  
Louisville  
ATTN: Chief, Engr Div  
Detroit  
ATTN: Chief, NCEED-T  
St. Paul  
ATTN: Chief, ED-D  
ATTN: Chief, ED-F  
Chicago  
ATTN: Chief, NCCCO-C  
ATTN: Chief, NCCED-F  
Rock Island  
ATTN: Chief, Engr Div  
ATTN: Chief, NCREO-F  
St. Louis  
ATTN: Chief, ED-D  
Kansas City  
ATTN: Chief, Engr Div  
Omaha  
ATTN: Chief, Engr Div  
New Orleans  
ATTN: Chief, LMNED-DG  
Little Rock  
ATTN: Chief, Engr Div  
Fort Worth  
ATTN: Chief, SWFED-D  
ATTN: Chief, SWFED-F  
Galveston  
ATTN: Chief, SWGAS-L  
ATTN: Chief, SWGCO-C  
ATTN: Chief, SWGED-DC  
Albuquerque  
ATTN: Chief, Engr Div  
Los Angeles  
ATTN: Chief, SPLED-F  
San Francisco  
ATTN: Chief, Engr Div  
Sacramento  
ATTN: Chief, SPKED-D  
ATTN: Chief, SPKCO-C  
Far East  
ATTN: Chief, Engr Div  
Portland  
ATTN: Chief, DB-6  
ATTN: Chief, FM-1  
ATTN: Chief, FM-2  
Seattle  
ATTN: Chief, NPSCO  
ATTN: Chief, NPSEN-FM  
ATTN: Chief, EN-DB-ST  
Walla Walla  
ATTN: Chief, Engr Div  
Alaska  
ATTN: Chief, NPASA-R

US Army Engineer Division  
New England  
ATTN: Chief, NEDED-T  
ATTN: Laboratory  
ATTN: Chief, NEDCO  
Middle East (Rear)  
ATTN: Chief, MEDED-T  
North Atlantic  
ATTN: Chief, NADEN  
South Atlantic  
ATTN: Laboratory  
ATTN: Chief, SADEN-TC  
ATTN: Chief, SADEN-TS  
Huntsville  
ATTN: Chief, HMD-ES  
ATTN: Chief, HMD-M  
ATTN: Chief, HMD-SR  
Lower Mississippi  
ATTN: Chief, LMVED-G  
Ohio River  
ATTN: Laboratory  
ATTN: Chief, Engr Div  
Missouri River  
ATTN: Chief, MRDED-G  
ATTN: Laboratory  
Southwestern  
ATTN: Laboratory  
ATTN: Chief, SWDED-MA  
ATTN: Chief, SWDED-TG  
South Pacific  
ATTN: Laboratory  
Pacific Ocean  
ATTN: Chief, Engr Div  
ATTN: FM&S Branch  
ATTN: Chief, POED-D  
North Pacific  
ATTN: Laboratory  
ATTN: Chief, Engr Div

Facilities Engineer  
Ft. Benning, GA 31905  
ATTN: ATZB-FE-EP  
ATTN: ATZB-FE-BG

AF/PREEU  
Bolling AFB, DC 20332

AFESC/PRT  
Tyndall AFB, FL 32403

Tinker AFB, OK 73145  
2854 ABG/DEEE

Patrick AFB, FL 32925  
ATTN: XRQ

McClellan AFB, CA 95652  
2852 APG/OE

Little Rock AFB  
ATTN: 314/DEEE

Naval Facilities Engr Command  
ATTN: Code 04  
ATTN: Code 2013 C  
Alexandria, VA 22332

Port Hueneme, CA 93043  
ATTN: Library (Code LOBA)  
ATTN: Merrill Library

Commander (Code 2636)  
Naval Weapons Center  
China Lake, CA 93555

Washington, DC  
ATTN: Bldg Research Advisory Board  
ATTN: Library of Congress (2)  
ATTN: Federal Aviation Administration  
ATTN: Dept of Transportation Library  
ATTN: Transportation Research Board

Rock Island Arsenal (12)  
ORCIS-RI-IB/M. Flaherty

Sierra Army Depot (12)  
ATTN: FE/M. Balerviez

Shahin, Mohamed Y.

Pavement evaluation and repair recommendation, Sierra Army Depot, Amedee  
Air Strip. -- Champaign, IL : Construction Engineering Research Laboratory ;  
Springfield, VA : available from NTIS, 1980.  
62 p. (Technical report ; M-283)

1. Sierra Army Depot, C. 2. Air bases -- runways. 3. Pavements --  
maintenance and repair. I. Title. II. Series: U.S. Army Construction  
Engineering Research Laboratory. Technical report ; M-283.